

Partial Estimate for Single Family Home Remodel

Item	Description	Qty	Unit	Price
01 Siding				
1.045.	16" MAIBEC CEDAR SHAKE INCLUDES SOFFIT AND FASCIA WORK 5" EXPOSURE	600	SF	
02 Windows and trim				
2.65.	ANDERSEN TILT WASH DOUBLE HUNG WINDOWS WHITE WITH FULL SCREENS Tw3046	5	EA	
03 Plumbing				
3.541.	PLUMBING LABOR AS PER PLAN			
	\$5000 Fixture allowance	1	EA	
04 Heating and cooling				
4.321.	INSTALL RUUD 90% HIGH EFFICIENCY FURNACE AND CENTRAL AIR 13 SEER CONDENSER UNIT	1	EA	
05 Electrical				
5.135.	ELECTRICAL AS PER PLAN			
	\$3200 Electrical allowance	1	EA	
06 Insulation				
6.001.	KRAFTBACK R-30 INSULATION	450	SF	
07 Interior walls				
7.003.	½" GYPSUM DRYWALL	1200	SF	
08 Millwork and trim				
8.135.	TRIM WINDOWS AND DOORS	11	EA	
8.592.	6" NECK BASE PAINT GRADE	300	LF	
Total price (this page)				\$30,275